

- » **High-performance homes effort to date**
- » **Model home prototype**
- » **Innovations in home construction**
- » **3D printed home project is born**
- » **Help us design the project**
- » **Questions**

Funding Matters

» Funding for housing is critical

- But...

» What about...


- Design of the home
- Size of the home
- Location of the home
- Home livability/accessibility
- Materials used
- Techniques applied
- Operations and maintenance



High-Performance Homes Effort to Date

» Iowa Green Streets Criteria

- Integrated Design
- Location & Neighborhood Fabric
- Site Improvement
- Water
- Operating Energy
- Materials
- Healthy Living Environment
- Operations & Maintenance



2020
IOWA GREEN STREETS CRITERIA

updated September 2020




IOWA
economic development

High-Performance Homes Effort to Date







				Solar Ready	Solar Ready
				Eff. Comps.& H ₂ O	Eff. Comps.& H ₂ O
				EPA Indoor Air Package	EPA Indoor Air Package
				Optimized Duct Location	Optimized Duct Location
		HVAC QI with WHV	HVAC QI with WHV	HVAC QI with WHV	HVAC QI plus HRV
		Water Management	Water Management	Water Management	Water Management
Independent HERS Verif.		Independent HERS Verif.	Independent HERS Verif.	Independent HERS Verif.	Independent PHIUS Verif.
IECC 2009 Enclosure	IECC 2012 Enclosure	IECC 2009 Enclosure	IECC 2012 Enclosure	IECC 2015 Encl./ES Win.	Ultra-Efficient Enclosure
HERS 85-90	HERS 70-80	HERS 65-75	HERS 55-65	HERS 48-55	HERS 35-45
IECC 2009	IECC 2012	ENERGY STAR v3	ENERGY STAR v3.1	ZERH	PHIUS+


High-Performance Homes Effort to Date



High-Performance Homes Effort to Date



(Image: Building America Solution Center)
Raised-Heel Truss
www.apawood.org/raised-heel-trusses



RESOURCES

- Advanced Energy: Comprehensive design and installation guidelines. [www](http://www.advancedenergy.com)
- Building Science Corporation: Features articles on conditioned crawl space foundations and slabs, or high R-value walls topics at buildingscience.cc
- U.S. Department of Energy, Office of Energy Efficiency & Renewable Energy: Downloads on best building practices. energy.gov/eere/buildings/building-america-bringing-building-innovations-market



Slab Insulation





Capillary Break

High-Performance Homes Effort to Date

» Design Consultations

- Architecture
- Planning
- Living Infrastructure
- Landscape Architecture
- Mechanical/Electrical Engineering
- High-Performance Construction
- Building Science



» Prototype Home Project

- Goals

- Affordability - Study the drivers of the cost of the home and respond with appropriate design strategies to balance the overall cost of the home.
- Adaptability – Considering the need for housing in Iowa for independent seniors and young families, investigate a design that is adaptable.
- Energy Efficiency – Evaluate through energy modeling various strategies to increase energy efficiency beyond current code compliance and look to the DOE Zero Energy Ready Home (ZERH) program for applicability to the design.

Prototype Home

Lead Design Team:

Kevin Nordmeyer, AIA

BNIM

Aaron Hauptmann, Assoc. AIA

BNIM

Design Collaborators:

Dan McGuire

The Element Group

HERS Rater

Michael Boerst

The Element Group

Energy Consultant

David Yocca, FASLA

Landscape Architect

Matt Faber, PE

KCL Engineering

Bill McAnally


McAnally Consulting

Construction Specialist

Prototype Home

» Prototype Process

- Banker / Lender
- Residential Contractors
- Realtor
- Hamburg Mayor and City Clerk



Prototype Home

» Prototype Concepts

- Option 1: Base Home: 1196 sf – 2 Bedroom, 1 Bathroom, Slab-on-Grade
- Option 2: 1 ½ Story Home: 1841 sf – 4 Bedroom, 2 Bathroom, Slab-on-Grade
- C. Option 3: 1 ½ Story Home: 1841 sf – potential 5 Bedroom, 3 Bathroom, Slab-on Grade - With Basement




Figure 3: Prototype Plans and Sections

» Prototype Performance

- Modeled home performance to:
 - Baseline Iowa energy code (IECC 2012)
 - 2018 IECC
 - DOE Zero Energy Ready Home
 - 2 ACH 50
 - All-electric home
 - Air Source Heat Pump (9 HSPF, 16 Seer)
 - Balanced ventilation w/recovery
 - 2.0 EF Heat pump water heater
 - Energy Star Appliances - all electric
 - 2x4 advanced framing, no cavity insulation, 4" of rigid insulation outboard
- Results
 - All 3 home concepts with energy modifications above met DOE ZERH home energy rating system requirement of HERS Index 48-55.

Prototype Home

» Cost Analysis

NAHB Survey Data		2019 data	2020	2021	2021 Lumber adjustment
NAHB data from Figure 7 data and appendix report					
Average Finished Floor Area		2594			
Construction Cost	\$	296,652	\$ 307,034.82	\$ 317,781.04	\$ 364,210.24
\$/sf calculated on finished area	\$	114.36	\$ 118.36	\$ 122.51	\$ 140.40
Total Sale Price of Home	\$	485,127	\$ 502,106	\$ 519,680	\$ 566,109.37
Includes total costs including land and other overhead, profit, etc.					
\$/sf calculated on finished area	\$	187.02			\$ 218.24
Comparable Iowa Home - planned build 2021 - Western Iowa					
Finished Floor Area		1100 w/bsmt			
Estimated Construction Cost	\$	185,000			
\$/sf calculated on finished area	\$	168.18	Construction only		
Total Sale Price Estimate	\$	251,250			
Includes total costs including land assumptions, overhead, etc.					
		w/bsmt			
\$/sf calculated on finished area	\$	228.41	Sale Price		
Comparable Home - Waukee, Iowa					
		2019	2020	2021	
Finished Floor Area		1643	3.50%	3.50%	
Sale Price	\$	338,000	\$ 349,830.000	\$ 362,074.05	
\$/sf finished area (has basement)	\$	205.72	\$ 212.92	\$ 220.37	
Range used to estimate probable costs for IEDA Prototype Home Concepts					
Construction Cost Range	\$	142.25	\$ 172.25		
Sale Price Range	\$	220.25	\$ 232.25		
Includes Incremental ZERH Costs noted below					
Cost Ranges for Prototype Homes					
			Option 1B	Option 2B	Option 3B
Area			1196	1841	1841
Construction cost range	\$	142.25	\$ 170,131	\$ 261,882	\$ 261,882
	\$	172.25	\$ 206,011	\$ 317,112	\$ 317,112
Sale Price Range	\$	220.25	\$ 263,419	\$ 405,480	\$ 405,480
	\$	232.25	\$ 277,771	\$ 427,572	\$ 427,572
Sale Price Accounting for no basement (1B,2B)	\$	(8,000)	\$ 255,419	\$ 397,480	\$ 405,480
	\$	(12,000)	\$ 265,771	\$ 415,572	\$ 427,572
ZERH Incremental Costs					
		2015	2019	2020	2021
Incremental Costs					
2012 IECC to ZERH		\$ 4,403	\$ 4,557	\$ 4,717	\$ 4,882
finishe area	2200			\$/sf	\$ 2.22

Figure 5: Cost Calculations – green areas have been added – not from NAHB

Prototype Home

» Cost Analysis

Cost Ranges for Prototype Homes			Option 1B	Option 2B	Option 3B
Area			1196	1841	1841
Construction cost range	\$ 142.25		\$ 170,131	\$ 261,882	\$ 261,882
	\$ 172.25		\$ 206,011	\$ 317,112	\$ 317,112
Sale Price Range	\$ 220.25		\$ 263,419	\$ 405,480	\$ 405,480
	\$ 232.25		\$ 277,771	\$ 427,572	\$ 427,572
Sale Price Accounting for no basement (1B,2B)	\$ (8,000)		\$ 255,419	\$ 397,480	\$ 405,480
	\$ (12,000)		\$ 265,771	\$ 415,572	\$ 427,572
ZERH Incremental Costs					
		2015	2019	2020	2021
Incremental Costs					
2012 IECC to ZERH		\$ 4,403	\$ 4,557	\$ 4,717	\$ 4,882
finishe area	2200			\$/sf	\$ 2.22

Figure 5: Cost Calculations – green areas have been added – not from NAHB

Prototype Home




Energy Information								PV system Energy Production					
Climate Zone 5		Des Moines, Iowa							6kw	7kw	8kw	9kw	10kw
Model	HERS	Heating (kwh/yr)	Cooling (kwh/yr)	Water Heating (kwh/yr)	Lights and Appliance s (kwh/yr)	Total (kwh/yr)	Monthly Average (kwh/yr)	% Energy Savings Over Baseline	kwh/yr				
Baseline 1	96	9525	1260	4132	6787	21704	1809		kwh/mo -avg	720	840	960	1079
Option 1B	49	3839	615	879	3733	9066	756	58.2%					
Energy Modeling Information								PV system Energy Production					
Climate Zone 6		Waterloo, Iowa							6kw	7kw	8kw	9kw	10kw
Model	HERS	Heating (kwh/yr)	Cooling (kwh/yr)	Water Heating (kwh/yr)	Lights and Appliance s (kwh/yr)	Total (kwh/yr)	Monthly Average (kwh/yr)	% Energy Savings Over Baseline	kwh/yr				
Baseline 1	93	12485	967	4396	6759	24607	2051		kwh/mo -avg	702	819	936	1052
Option 1B	50	5363	381	938	4073	10755	896	56.3%					

Cost Ranges for Prototype Homes		Option 1B
Area		1196
Construction cost range	\$ 142.25	\$ 170,131
	\$ 172.25	\$ 206,011
Sale Price Range	\$ 220.25	\$ 263,419
	\$ 232.25	\$ 277,771
Sale Price Accounting for no basement (1B,2B)	\$ (8,000)	\$ 255,419
	\$ (12,000)	\$ 265,771

Prototype Home

bnim

bnim Architects
271 South Avenue, Suite 100, Des Moines, IA 50309
www.bnim.com



- 001 Cover sheet
- 002 General notes
- 003 Plan / Sections - 2 bedroom Slab-on-grade
- 004 Elevations - 2 bedroom slab-on-grade
- 005 Plan / Sections - 4 bedroom occupied attic
- 006 Elevations - 4 bedroom occupied attic
- 007 Wall sections
- 008 Wall types and basement option
- 009 Roof plan / site concept
- 010 Development orientation options
- 011 Performance criteria
- 012 Green Streets / energy
- 013 Green Streets checklist
- 014 Green Streets checklist

Schematic Design Documents

Iowa - High Performance Prototype Home

Iowa Energy Office
Iowa Economic Development Authority

Project No: 200223.00

May 1, 2021

1 Story Option Plans

003

Copyright © 2020 BNIM Architects

Prototype Home

bnim

BNIM Architects
371 South Avenue, Suite 100, Des Moines, IA 50309
www.bnim.com

001	Cover sheet
002	General notes
003	Plan / Sections - 2 bedroom slab-on-grade
004	Elevations - 2 bedroom slab-on-grade
005	Plan / Sections - 4 bedroom occupied attic
006	Elevations - 4 bedroom occupied attic
007	Wall sections
008	Wall types and basement option
009	Roof plan / site concept
010	Development orientation options
011	Performance criteria
012	Green Streets / energy
013	Green Streets checklist
014	Green Streets checklist

Schematic Design Documents

Iowa - High Performance Prototype Home

Iowa Energy Office
Iowa Economic Development Authority





Project No: 20023.00

May 1, 2021

1 Story Option Elevations

004

Copyright © 2021 BNIM Architects



Prototype Home

bnim

BM&B Architects
317 South Avenue, Suite 100, San Marcos, CA 92069
www.bmba.com

001	Cover sheet
002	General notes
003	Plan / Sections - 2 bedroom slab-on-grade
004	Elevations - 2 bedroom slab-on-grade
005	Plan / Sections - 4 bedroom occupied attic
006	Elevations - 4 bedroom occupied attic
007	Wall sections
008	Wall types and basement option
009	Roof plan / site concept
010	Development orientation options
011	Performance criteria Green Streets / energy
012	Green Streets checklist
013	Green Streets checklist
014	Green Streets checklist

Schematic Design Documents

Iowa - High Performance Prototype Home


Iowa Energy Office
Iowa Economic Development Authority

Project No: 20023.00

May 1, 2021


Details

007



1 Detail Section - Foundation and Sill

3 Exterior Wall - 2 Story Option



4 Vented Attic Detail

5 Exterior Wall - 1 Story Option

Innovations in Home Design & Construction

» Cost still too high

Cost Ranges for Prototype Homes			Option 1B	Option 2B	Option 3B
Area			1196	1841	1841
Construction cost range	\$ 142.25		\$ 170,131	\$ 261,882	\$ 261,882
	\$ 172.25		\$ 206,011	\$ 317,112	\$ 317,112
Sale Price Range	\$ 220.25		\$ 263,419	\$ 405,480	\$ 405,480
	\$ 232.25		\$ 277,771	\$ 427,572	\$ 427,572
Sale Price Accounting for no basement (1B,2B)	\$ (8,000)		\$ 255,419	\$ 397,480	\$ 405,480
	\$ (12,000)		\$ 265,771	\$ 415,572	\$ 427,572
ZERH Incremental Costs					
		2015	2019	2020	2021
Incremental Costs					
2012 IECC to ZERH		\$ 4,403	\$ 4,557	\$ 4,717	\$ 4,882
finishe area	2200			\$/sf	\$ 2.22

Figure 5: Cost Calculations – green areas have been added – not from NAHB

Innovations in Home Design & Construction

» How else can we lower costs?

- $\text{Cost} = \text{Size} + \text{Quality} + \text{Materials/Methods} + \text{Time}$
 - We've attempted to address size
 - We've worked on improving quality with same or reduced costs
 - What could we address materials and time?

Innovations in Home Design & Construction

» How can we shorten the time to construct a home?

- 3D printing
- Pre-fabrication
 - (EPS) Structural insulated panels
 - Superior Walls
 - Modular construction
 - Manufactured homes
 - CNC technology
 - Digital design

Innovations in Home Design & Construction



SCJournal

» ISU proposal for 3D Affordable Innovative Technologies Housing

- IEDA reviewing

» Partners:

- » Iowa State University
- » Iowa Central CC
- » Ames
- » BNIM
- » Brunow Construction
- » Hubbell Realty
- » Iowa Association of Realtors
- » Iowa DPS
- » Iowa Habitat for Humanity
- » Iowa Housing Partnership
- » Iowa League of Cities
- » Lincoln Savings Bank
- » Matthew 25
- » McAnally Consulting
- » McClure Engineering
- » Sukup Manufacturing
- » The Element Group
- » Vermeer
- » You ???

3D Affordable Innovative Technologies Home

[HOME](#)[PROJECTS](#)[FEATURES](#)[CAREERS](#)[FAQ's](#)[VR](#)[NEWS](#)[CONTACT US](#)

Riverhead, New York

First 3D printed house for sale.

Bedrooms

3

Bathrooms

2

Area

1,407²


3D Affordable Innovative Technologies Home

[HOME](#)[PROJECTS](#)[FEATURES](#)[CAREERS](#)[FAQ's](#)[VR](#)[NEWS](#)[CONTACT US](#)

Frequently asked questions.

We're developing new technology, so it's natural to have some questions. Here are a few that we hear often.

- + What is the lifetime of the printer?
- + Is SQ4D a publicly traded company?
- + Can you tell me more about SQ4D's ARCS 3D printer?



3x

Faster than traditional

40%

Reduction in total

6k+

PSI results of compressive


3

Total laborers required for

3D Affordable Innovative Technologies Home

UNCLASSIFIED//FOUO

ICON 3D Printed Barracks




TXARNG Camp Swift Training Center:

- Largest TXARNG training site
- Centrally located to support TXARNG units
- Pre-deployment training for T10 missions
- RSOI and Training for DSCA missions
- 1600 beds, 2xDFAC, Ranges, Training Areas
- 25% Relocatable Transient Training Barracks
 - 13 "Swift Temporary Barracks" = STB
 - Beyond the end of lifecycle
 - Very inefficient to operate
 - Non-viable to maintain
- Opportunity to Replace STBs with permanent more efficient and improved soldier quality of life

Barracks of the Future:

- Approx. 5,000 SF TT Barracks
- Innovative Design and Construction
- Construction Scale 3D Printed Building
- Very High Efficiency and Long Life
- Reduced O&M Cost
- Will replace 2 Relocatable / Temp barracks
- Will house up to 72 soldiers (36 per bay)



TEXAS ARMY NATIONAL GUARD

3D Affordable Innovative Technologies Home

UNCLASSIFIED//FOUO


INNOVATIVE BARRACKS INITIATIVE

Engaging innovative technology and partnerships to help resolve our shortage of transient training barracks

Camp Bowie

UMMC TT BARRACKS


- Traditional D-B-B project \$3M
- 7,261 SF TT Barracks
- Traditional Construction Methods



Camp Swift

ICON 3D

- AFWERX SBIR II ANG Project
- 5,000 SF TT Barracks
- Construction Scale 3D Printed Building
- Innovative Design
- High Efficiency / Reduced O&M



Camp Maxey

MAX STEEL

- AFWERX SBIR II ANG Project
- 3,200 SF TT Barracks
- Modular Steel Barracks
- Long Life
- Very High Efficiency / Reduced O&M



TEXAS ARMY NATIONAL GUARD

3D Affordable Innovative Technologies Home

Prescient® | Revolutionize the Building Environment®

[ABOUT](#) [APPROACH](#) [PROJECTS](#) [NEWS & INSIGHTS](#) [CAREERS](#) [CONNECT](#) | [Q](#)

ATTAINABLE HOUSING FOR ALL

We impact time, money and risk at every stage of a project

WHAT WE DO

WHAT WE'VE DONE

3D Affordable Innovative Technologies Home



[ABOUT](#) ▾ [PROCESS](#) ▾ [ADVANTAGES](#) [PROJECTS](#) ▾ [CONTACT](#)

Latest News

05/17/2021

The Built World TV Show - Smart City

02/18/2021

2021 Building Tech 50 List

12/14/2020

Greenwich Village's Carbone getting creative with outdoor dining

12/12/2020

Mobile isolation units to treat COVID-19 patients

SHAPING THE
FUTURE OF


URBAN
DEVELOPMENT

3D Affordable Innovative Technologies Home

BOXABL



Publication Number
US 8,733,029 B2



boxabl
March 15



Monday Patent Post ✍️

Boxabl has 17+ patent filings and growing. With these patents, we are creating the world's most advanced building system and change the lives of billions of people around the globe. 🏠🌍

Be sure to look up the patent number to learn more!

#boxabl #weld #mechanicalengineering
#mechanical #engineer #innovation #mansion
#homeforsale #homesforsale #cncmachining
#instamachinist #housegoals #steel

3D Affordable Innovative Technologies Home

[Technology](#)[How It Works](#)[Safety](#)[Completed Projects](#)[About](#)[Careers](#)[Get in Touch →](#)

Move the Earth

Transform any excavator into a trenching robot with an easy-to-install aftermarket upgrade.

[How It Works →](#)

3D Affordable Innovative Technologies Home

IOWA NEST RESIDENCE

A Net Zero Energy Home at Conventional Cost

[Overview](#)

[The House](#)

[The Design Process](#)

[The Build](#)

[The Data](#)

[The Team](#)

[News & Events](#)

AUGUST 25, 2016 BY CARL STERNER

Iowa Nest Residence: Net Zero Energy at Conventional Cost



3D Affordable Innovative Technologies Home



3D Affordable Innovative Technologies Home



3D Affordable Innovative Technologies Home



Products

Rooms

What are you looking for?



Planners > Kitchen planner

Kitchen planner

Thinking about a new kitchen but don't know where to start? Our kitchen planner is here to help. Find out how your new kitchen could look like in just a few steps.



3D Affordable Innovative Technologies Home



File Edit

Item list/Total price

Notes

Print

Save

Create a profile or log in | IKEA USA



The IKEA website uses cookies, which make the site simpler to use. [Find out more about browser cookies.](#)

Search products

Your room layout



Room Shape and Size

Add doors

Add windows

Choose flooring

Walls & Ceiling

Add Fixtures

Additional Structures

Add Decorations


> Kitchen & Appliances

> Dining tables & chairs

> Office

> Kitchen - Change All at once

> Your list so far



ROOM LAYOUT

(inch, 12 inches = 1 foot)

You may also resize the room by clicking on a wall and moving it.

Wall A

240

Wall B

180

Ceiling


100

Apply

Lock my measurements



This will lock the dimensions of the room, including ceiling, shapes and placement of doors and windows.



Rectangular



Open room solution



Indent NorthEast Corner



Indent NorthWest Corner



Indent SouthEast Corner



Indent SouthWest Corner

<https://kitchenplanner.ikea.com/us/UI/Pages/VPUI.htm>

<https://www.forbes.com/sites/jessedamiani/2020/12/01/varjo-announces-third-generation-human-eye-resolution-vr-3-and-xr-3-headsets/?sh=2f337e763d1d>

3D Affordable Innovative Technologies Home




IOWA CENTRAL
COMMUNITY COLLEGE

IOWA STATE UNIVERSITY
OF SCIENCE AND TECHNOLOGY

IOWA
economic development

3D Affordable Innovative Technologies Home



<https://www.opendesign.com/products>


openBIM® PRINCIPLES

The buildingSMART Data Dictionary is a service from buildingSMART International. The Data Dictionary actively delivers an open and neutral solution to drive digital transformation and automation in the built asset industry.

- ✓ You own your data
- ✓ Data Security
- ✓ Usage Analysis
- ✓ Extend IFC
- ✓ Vendor neutral
- ✓ Linked data
- ✓ Always open
- ✓ openAPI spec
- ✓ ISO 12006-3 (IFD)
- ✓ ISO 23386/7 (PDT)
- ✓ ISO 16739-1 (IFC)
- ✓ ISO 29481 (IDM)
- ✓ CEN TC442
- ✓ OTL Support

<https://technical.buildingsmart.org/services/bsdd/>

3D Affordable Innovative Technologies Home



<https://www.forconstructionpros.com/construction-technology/article/21295561/six-factors-to-consider-when-adding-drones-to-your-construction-business#&gid=1&pid=10>

<https://www.unmannedsystemstechnology.com/2021/05/lidar-vs-photogrammetry-for-uav-encroachment-surveying/>

<https://varjo.com/products/xr-3/>

3D Affordable Innovative Technologies Home



<https://www.builtrobotics.com/solutions/projects>

3D Affordable Innovative Technologies Home



<https://www.3dprintingmedia.network/first-3d-printed-house-in-germany-inaugurated-by-minister-of-construction/>



<https://www.latimes.com/business/realestate/hot-property/la-fi-hp-arospace-shipping-containers-20190621-story.html>



<https://www.dwell.com/article/casita-prefab-adu-boxabl-c89a38cd>

Comments – Questions?



Contact Information

Jeff Geerts

Special Projects Manager

Iowa Economic Development Authority

1963 Bell Ave, Ste 200

Des Moines, Iowa 50315

515-348-6211

Jeff.geerts@iowaeda.com

Pete Evans AIA IDSA

Assistant Professor, Industrial Design Department

Coordinator, Forward Learning Experience

Iowa State University

pmevans@iastate.edu